

January 31, 1997

Mr. Andrew Shively Vermont ANR/DEC Waste Management Division 103 South Main Street / West Building Waterbury, VT 05671-0404

RE: Investigation of Suspected Subsurface Petroleum Contamination at Mad River Glen Ski Area, Route 17, Fayston, VT (VTDEC Site # 96-2061)

Dear Mr. Shively:

Please find enclosed a summary report for the site investigation conducted for the Mad River Glen Cooperative. This report is forwarded to the Vermont Department of Environmental Conservation (VTDEC), on behalf of Mad River Glen Cooperative, Inc. Please contact me if you have any questions or comments.

Sincerely,

Erik C. Sandblom

Engineer

Enclosure

cc: Bob Mazza, Mad River Glen Coop.

# REPORT ON THE INVESTIGATION OF SUSPECTED SUBSURFACE PETROLEUM CONTAMINATION

**JANUARY 31, 1997** 

Site Location:
MAD RIVER GLEN SKI AREA
ROUTE 17
FAYSTON, VERMONT

.6. W 5 10 s 31 .8.

**VTDEC SITE #96-2061** 

# Prepared For:

MAD RIVER GLEN COOPERATIVE, INC. P.O. BOX 1089 FAYSTON, VERMONT 05673

Prepared By:



P.O. Box 943 / 19 Commerce Street Williston, VT 05495 (802) 865-4288

# TABLE OF CONTENTS

I.	INTR	RODUCTION								
II.	SITE A. B.	BACKGROUND Site History Site Description	1 2							
III.	INVE	STIGATIVE PROCEDURES								
	A. B. C. D. E. F.	Monitoring Well and Soil Boring Installation Determination of Groundwater Flow Direction and Gradient Groundwater Sample Collection and Analysis Water Supply Well Sample Collection and Analysis Inspection of Stockpiled Soils Sensitive Receptor Risk Assessment	2 4 4 5 5 5							
IV.	CONCLUSIONS									
٧.	RECO	OMMENDATIONS	7							
APPI	ENDICI	ES .								
	A.	SITE MAPS 1) Site Location Map 2) Site Area Sketch 3) Site Map 4) Groundwater Contour Map								
	B.	MONITORING WELL / SOIL BORING LOGS								
	C.	GROUNDWATER QUALITY SUMMARY DATA								
	Ď.	SOIL SAMPLE ANALYSIS DATA SUMMARY								
	E.	GROUNDWATER LIQUID LEVEL DATA								
	F.	LABORATORY ANALYSIS REPORTS								

#### I. INTRODUCTION

The following report summarizes an investigation of suspected subsurface petroleum contamination that was conducted at Mad River Glen Ski Area, located on Route 17 in Fayston, Vermont. This work has been conducted by Griffin International, Inc. (Griffin) for Mad River Glen Cooperative, Inc. The Vermont Department of Environmental Conservation (VTDEC) requested that this work be completed in a letter addressed to Mr. Bob Mazza, of Mad River Glen Cooperative, Inc., from Mr. Chuck Schwer, of the VTDEC, dated October 22, 1996. All work at the site was conducted in accordance with the October 29, 1996 Work Plan and Cost Estimate prepared by Griffin, which was approved by the VTDEC in a letter from Mr. Andrew Shively, of the VTDEC, to Mr. Mazza, dated November 13, 1996.

Work conducted at the site includes the installation of four groundwater monitoring wells and one soil boring, and the subsequent collection and analysis of soil and groundwater samples.' A groundwater contour map was generated for the vicinity of the monitoring wells. Water samples were collected for analysis from three on-site water supply wells. In addition, a sensitive receptor risk assessment was conducted to assess the risk that subsurface petroleum contamination at the site may pose to sensitive receptors in the area.

#### II. SITE BACKGROUND

## A. Site History

On August 20, 1996, two underground storage tanks (USTs), both used to contain No. 2 fuel oil, were permanently closed and removed from the ground as part of routine UST system replacements. UST #1 was 3,000 gallons in capacity, and located along the northern edge of the Basebox Building (see Site Map in Appendix A). UST #2 was 630 gallons in capacity and located on the eastern side of the patrol building. Petroleum contamination was detected in soils surrounding UST #1 during the UST removal inspection conducted by Griffin. Approximately one cubic yard of petroleum contaminated soil was stockpiled and encapsulated in a polyethylene liner on-site. Residual petroleum contaminated soil containing 8 to 15 parts per million (ppm) volatile organic compounds (VOCs) as measured with a photo-ionization detector (PID) remained in the excavation due to buried power lines and the building foundation. VOCs were detected in soil in the excavation for UST #2 up to 110 ppm close to the water table. Approximately 14 cubic yards of petroleum contaminated soil from this excavation were stockpiled on-site in order to make room for the replacement UST.

As a result of the detected petroleum contamination in the subsurface at the site, the VTDEC requested that additional work be completed to further define the extent and degree of petroleum contamination in the vicinity of the two USTs. Mad River Glen Cooperative retained the services of Griffin to conduct the work requested by the VTDEC. A Work Plan and Cost Estimate, dated October 29, 1996, was sent to the VTDEC, with the approval of Mad River Glen Cooperative, Inc. The VTDEC approved the Work Plan and Cost Estimate in a letter dated November 13, 1996. This report summarizes the site investigation.

#### B. Site Description

Mad River Glen Cooperative, Inc. is located on the south side of Vermont Route 17 along the western edge of the Town of Fayston, Vermont (see Site Location Map in Appendix A). The property is operated as a ski area which includes several chair lifts, a restaurant / base lodge / ticket office (Basebox), a nursery, first aid / ski patrol, administrative offices, ski rental, retail store, and a maintenance garage. The only public utilities at the site are telephone and electric power. Four drilled water supply wells are located on-site which supply water to the ski area. Two wells (SW-1 and SW-2) are located on the north side of the Basebox, adjacent to the main Mill Brook tributary. A third well (Nursery Well, or SW-3) is located near the east side of the Cricket Club Nursery daycare. The fourth well is located on an adjacent property owned by Richard Dale (Hutch Well) to the north.

Nearly the entire subject property consists of natural terrain. The property is abutted primarily by residences, many of which are used seasonally. Sugarbush Ski Area boarders Mad River Glen to the south. The western border of the property is approximated by the ridge of Stark Mountain. Approximately 50 residential lots are situated near the northern border of the property along Route 17.

The property is drained by several streams on the mountain which are tributaries of Mill Brook. These streams generally flow from west to east toward the base lodge area. The 1970 Surficial Geologic Map of Vermont indicates that the overburden at the subject property consists of glacial till. Overburden thicknesses in the area are likely less than 50 feet. Bedrock in the area is mapped primarily as schist of the Underhill Formation, according to the 1961 Centennial Geologic Map of Vermont. Groundwater flow direction in the base area is to the north, toward Mill Brook. The water table beneath the base area of the property varies from 2.5 to 12.0 feet below grade.

#### III. INVESTIGATIVE PROCEDURES

## A. Monitoring Well and Soil Boring Installation

On December 3 and 4, 1996, four groundwater monitoring wells (MW-1, MW-2, MW-3, and MW-4) were installed adjacent to and in the vicinity of the former location of UST #2, and a soil boring was drilled in the presumed downgradient direction from the former location of UST #1. The locations of the wells and soil boring are displayed on the Site Map in Appendix A. The company conducting the drilling services was Green Mountain Boring, Inc. of Barre, Vermont. All drilling and well installation activities were conducted under the direct supervision of a Griffin engineer.

Monitoring wells and the soil boring were advanced with the use of a 4.25 inch inner diameter hollow stem auger drill rig. Undisturbed soil samples were collected with the use of a

split spoon sampler at a minimum of five foot intervals. Soil types from each boring were classified and logged in detail. Each soil sample was screened in the field for VOCs with a properly calibrated H-Nu HW-101 PID. All wells were developed by hand using a bailer immediately following installation.

The wells were constructed of factory slotted, two-inch diameter PVC pipe with a slot size of 0.010 inch and a schedule 40 PVC riser. The length of the screen and riser varied depending on the depth of the well and the location of the water table in the bore hole. Specific well construction details are displayed in the detailed well logs included in Appendix B. All wells were installed in accordance with Griffin protocols which comply with State and industry standards.

Soil encountered in the soil borings for all four monitoring wells consisted of dry, brown, fine sand and silt with a trace of fine gravel from the ground surface to approximately five feet below grade. Beyond five feet, soil typically consisted of medium to coarse sand and gravel with a trace of silt. Clay was encountered in samples collected from 10 to 12 feet below grade in the soil borings for MW-2 and MW-3. The water table in these two monitoring wells was detected at a significantly shallower depth that the other two monitoring wells, on the day of well installation. The measured water table depths for MW-1, MW-2, MW-3, and MW-4 were at 8.0 feet, 4.0 feet, 2.5 feet, and 6.5 feet below grade, respectively.

Dry, brown, medium to fine, sand and silt with a trace of gravel was encountered from grade elevation to five feet below grade in the soil boring drilled in the vicinity of UST #1 (SB-1). From seven to eight feet below grade, saturated medium to fine gravel till and silt was encountered over fine to medium gravel and very fine sand and silt. Crushed and whole rock till was encountered over saturated sand and silt from 11 to 13 feet below grade. The observed soil types are consistent with the glacial till description given on the Surficial Geologic Map of Vermont. Exploration was discontinued at 13 feet below grade. Although saturated soil samples were collected from seven to nine feet below grade, it is likely that the regional water table in the borehole is at 12 feet below grade. It is believed that the well consolidated, very fine sand and silt located at nine feet caused a perched water table in soil in this vicinity.

Maximum VOC concentrations detected in soil samples retrieved from the boreholes were 2.2 ppm at 10'-12' in MW-1, 6.0 ppm at 10'-12' in MW-2, 0.8 ppm at 5'-7' in MW-3, 2.1 ppm at 10'-10¼' in MW-4, and 0.2 ppm at 9'-11' and 13' in SB-1.

A soil sample was collected from SB-1 at 12 feet below grade, the approximate depth of the regional water table in the borehole. The saturated soil sample was laboratory analyzed for BTEX (benzene, toluene, ethyl benzene, xylenes) and MTBE (methyl tertiary butyl ether). Sample analysis results are summarized in Appendix D. According to the results of the analysis, no BTEX constituents were detected above a detection limit of 51 ppb (parts per billion), or 0.05 ppm, and MTBE was not detected in the sample above a detection limit of 551 ppb (0.55 ppm).

# B. Determination of Groundwater Flow Direction and Gradient

The monitoring wells were allowed to stabilize for a period of approximately one week. On December 12, 1996, depth to water measurements were collected with the use of a Keck interface probe for all four site related wells. These measurements were subtracted from the top of casing elevations, which were determined relative to an arbitrary datum of 100 feet at the top of the casing for MW-1, to determine the water table elevation at each of the wells. From the monitoring well water table elevation data, the groundwater contours were interpolated onto the site map and the groundwater direction and gradient determined.

As displayed on the groundwater contour map included in Appendix A, the groundwater flow direction for December 12, 1996 in the vicinity of the monitoring wells, was generally to the north, toward the Mill Brook tributary, at a gradient of approximately 20%. This is considered to be an exceptionally steep hydraulic gradient; however, it is consistent with the relatively steep topography and high volume of surface water drainage to the Mill Brook tributary.

### C. Groundwater Sample Collection and Analysis

Following depth to water data collection, samples of the groundwater were collected from all four of the site related monitoring wells. No free phase petroleum product was observed in any of the monitoring wells. All samples were analyzed for BTEX and MTBE, common constituents of petroleum contamination, per EPA Method 602. Results of the laboratory analyses for those wells sampled on this date are summarized in Appendix C.

According to the results of the analyses, a very low level of dissolved petroleum contamination was detected in the sample collected from monitoring wells MW-3 and MW-4. Xylenes were detected in the sample collected from MW-3 at a concentration of 2.3 ppb, and benzene and toluene were each detected at a trace below quantitation level, which was 1.0 ppb. Toluene was detected in the sample collected from MW-4 at a concentration of 1.1 ppb and benzene was detected at trace below quantitation level of 1.0 ppb. No compounds were detected in the analyses at concentrations at or above applicable state groundwater standards. No compounds tested for in the analyses were detected in monitoring wells MW-1 or MW-2.

All samples were collected according to Griffin's groundwater sampling protocol which complies with industry and state standards. A concentration of 1.1 ppb of toluene and a trace concentration of xylenes (TBQ<1) were detected in the trip blank sample. The source of this contamination has been traced to the distilled water used to prepare the blank. This problem with the distilled water has since been addressed by Griffin. The toluene and xylenes measurements for the monitoring wells are not likely compromised. No equipment blank was collected, as disposable bailers were used for sample collection. Results of the duplicate sample indicate that adequate quality assurance and quality control (QA/QC) were maintained during collection, transportation and analysis of the samples. All samples were analyzed within the specified holding times.

# D. Water Supply Well Sample Collection and Analysis

Water samples were collected for analysis from three on-site water supply wells (SW-1, SW-2, and SW-3) on the day of groundwater sample collection. One sample was collected representative of both SW-1 and SW-2, as both wells are plumbed to the Basebox water distribution system. To collect individual samples from each well would require significant modification of the Basebox plumbing system, or well head access. The SW-1/SW-2 sample was collected from a sink in the kitchen of the cafeteria in the basebox. A second sample was collected from the drilled well that services the nursery and the patrol building (SW-3). This sample was collected from a sink located in the patrol building. Treatment systems are reportedly not connected to any of the sampled water supplies. No construction data is known regarding these three on-site supply wells, except that, according to site representatives, all wells are drilled.

All supply well samples were analyzed for BTEX and MTBE per EPA Method 602. The results of the sample analyses indicate that no compounds tested for in the analysis were detected in any of the samples collected from these water supplies.

## E. Inspection of Stockpiled Soils

A total of approximately 15 cubic yards of petroleum contaminated soil from the excavation of UST #1 and UST #2 remain stockpiled on-site at the top of the practice slope (double chair lift line #4 on area sketch), located approximately 800 feet to the north of the base box. The stockpile is completely encapsulated in a polyethylene liner. Soil samples were not collected for field screening with a PID during drilling or groundwater sample collection, as the surface of the stockpile was frozen. According to the UST Removal Inspection Report prepared by Griffin in August of 1996, the stockpiled soil contained an average VOC concentration of 49 ppm at the time of the UST removals.

#### F. Sensitive Receptor Risk Assessment

A receptor risk assessment was conducted to identify any known or potential receptors of residual contamination detected at Mad River Glen Cooperative, Inc. A visual survey was conducted at the time of drilling and groundwater sample collection. Based on these observations, a determination of the potential risk to identified receptors was conducted based on source proximity, groundwater flow direction, and contaminant concentration levels. Interviews and historical research were also conducted as part of the survey.

## Water Supplies

Four drilled supply wells service the water needs of the base area at the site. Two wells are located on the north side of the basebox building (SW-1 and SW-2), a third is located to the south of the nursery building (SW-3), and a fourth is located at the Hutch residential property to the east of the double No. 4 chair-lift, on the opposite side of the Mill Brook.

Given the separation distances between the Hutch well and the two former USTs, and given that the Hutch well is located on the opposite side of the Mill Brook from the two former USTs, this well is not likely at a significant risk of petroleum contamination impact from the two former USTs (UST #1 and UST #2). The two wells supplying the basebox are located within approximately 100 feet of UST #1, in a direction that is likely hydraulically upgradient or cross gradient. These wells are both drilled wells, presumably both installed into the bedrock aquifer. Given these assumptions, and that the level of petroleum contamination detected in the vicinity of the former UST is very low, the two basebox wells are not likely significantly at risk of petroleum contamination impact. According to sample analysis results, none of the petroleum compounds tested for as a part of this investigation were detected in SW-1, SW-2, or SW-3.

## Surface Waters

The only identified surface water that could potentially be at risk from petroleum contamination at Mad River Glen Cooperative is the Mill Brook, which flows downgradient of both UST #1 and UST #2. However, based on the low level of dissolved contamination detected in the overburden at the site, and the separation distance between the river and the former USTs, it is not likely that the Mill Brook is at significant risk of impact by petroleum contamination from the former USTs. The banks of the river were inspected on the days of drilling and groundwater sample collection. No evidence of petroleum contamination impact (such as sheens on the water surface, stressed vegetation, stained soil, or petroleum odors) were observed. The banks of the river were covered with ice and snow at the time of inspection.

# Buildings in the Vicinity

Several buildings are located in the vicinity of former UST #1 and UST #2, the closest of which are the basebox, located adjacent to UST #1 and the patrol building, located adjacent to UST #2. Both buildings are constructed upon concrete slab foundations which extend into site soils to create partial basements. Given the removal of petroleum contaminated soil in the vicinity of the USTs, and the very low level of petroleum contamination detected in soils and groundwater at the site, the majority of adsorbed petroleum contamination has likely been removed from the ground. Screening of the breathing space in the basements of the two buildings with a PID indicated that there were no VOCs above background levels. No complaints have been reported of petroleum odors within the building. Therefore, on-site buildings do not appear to be at risk of petroleum vapor impact.

#### IV. CONCLUSIONS

Based on currently available data regarding Mad River Glen Cooperative, located in Fayston, Vermont, the following conclusions are presented:

- 1) Very low concentrations of dissolved petroleum contamination have been detected in groundwater downgradient of a former fuel oil UST (UST #2) located near the ski patrol building at the subject property. Contamination levels detected at the site are well below applicable state groundwater standards. Some residual petroleum contamination may remain in the vadose zone in the immediate vicinity of UST #2; however, the majority of adsorbed petroleum contamination has most likely been removed, since no petroleum contaminants have been detected in groundwater from the monitoring well (MW-2) located directly adjacent to the UST.
- The screening and analysis results of soil samples collected from a soil boring drilled directly adjacent to former fuel oil UST #1 at the subject property indicate that no significant petroleum contamination remains in the subsurface in this vicinity.
- No identified sensitive receptors in the area are at significant risk of petroleum contamination impact due to the sufficient distance of receptors from the site and/or the very low levels of contamination detected at the site.
- Approximately 15 cubic yards of petroleum contaminated soil are stockpiled and encapsulated in a polyethylene liner at the site. Current VOC concentrations in the pile have not been determined due to the frozen nature of the soils. Petroleum contamination levels within the stockpile are expected to reduce over time due to natural process of degradation.
- 5) Over time, the natural processes of dilution, dispersion, and biodegradation will reduce contaminant concentrations in the subsurface at Mad River Glen Cooperative to non-detect.

#### V. RECOMMENDATIONS

Based on the above conclusions, the following recommendations are presented concerning petroleum contamination detected in the subsurface at Mad River Glen Cooperative, Fayston, Vermont:


Based on the results of groundwater and soil sample analyses, only very low concentrations of benzene and xylenes were detected in groundwater at the site. These concentrations are below state groundwater standards. Based on this fact and given that no sensitive receptors appear to be at risk of petroleum contamination, no further subsurface work is warranted at this site.

The soil stockpile at the site will be screened for VOCs in the Spring of 1997, in accordance with the Work Plan, after it thaws, with a properly calibrated PID. Several soil samples will be collected from within the stockpile and screened in accordance with Griffin's Jar / Polyethylene Bag Headspace Analysis Protocol. The plastic covering should be routinely inspected and maintained. It may be necessary to re-pile the soil on a new liner every 12 months depending on the condition of the liner. This will also aid in the more efficient reduction of contaminants in the pile by adding oxygen to the soil. Further recommendations regarding petroleum contaminated stockpiled soils will be presented following screening.

# APPENDIX A

# SITE MAPS

- 1) Site Location Map
  - 2) Site Area Sketch
    - 3) Site Map
- 4) Groundwater Contour Map




JOB #: 11964945 SOURCE: USGS- MOUNT ELLEN, VERMONT QUADRANGLE





# MAD RIVER GLEN COOPERATIVE FAYSTON, VERMONT

SITE LOCATION MAP


DATE: 1/14/97 DWG.#:1 SCALE: 1:24000 DRN.:SB APP.:ES







# APPENDIX B MONITORING WELL / SOIL BORING LOGS



WELL NUMBER MW2 PROJECT MAD RIVER GLEN COOPERATIVE Site LOCATION FAYSTON, VERMONT Sketch HILL BROOK ⊕<sup>M¥4</sup> DATE DRILLED 12/3/96 TOTAL DEPTH OF HOLE 12.0' DIAMETER\_ SCREEN DIA 2" LENGTH 7.0' SLOT SIZE 0.010" CASING DIA. 2" LENGTH 2.5' TYPE sch 40 pvc DRILLING CO. \_\_GMB \_\_DRILLING METHOD HSA DRILLER RON GARNEAU LOG BY E. SANDBLOM GRIFFIN INTERNATIONAL. INC WELL BLOWS PER DESCRIPTION/SOIL CLASSIFICATION DEPTH DEPTH NOTES 6" OF SPOON IN CONSTRUCTION (COLOR, TEXTURE, STRUCTURES) FEET FEET & PID READINGS ROAD BOX LOCKING WELL CAP 0 -CONCRETE · 1 · NATIVE BACKFILL 0'-5' Dry, brown, silty SAND with trace of fine gravel. 0.6 ppm ' 2 -BENTONITE 3 3 . WELL RISER 4.0' WATER TABLE 4 5 SAND PACK 5'-7'- 4/3/6/6 Saturated, brown, fine to medium coarse 6 -6 -SAND and SILT with gravel. 5.9 ppm WELL SCREEN 7 . 8 -8 - 9 -BOTTOM CAP · g · -10 --10 10'-12'- 3/6/6/12 Saturated, very fine SAND, SILT and -11 --11 -6.0 ppm CLAY, trace of gravel. -12 -12 UNDISTURBED BASE OF WELL AT 10.0' NATIVE SOIL END OF EXPLORATION AT 12.0' -13 -13 -14 -14 -15 -15 -16 -16 -17 --17 -18 -18 -19 -19 · -20 -20 -21 -21 22. -22 -23 -23 -24 -24 25 -25

WELL NUMBER MW3 MAD RIVER GLEN COOPERATIVE PROJECT Site I CATION FAYSTON, VERMONT Sketch MILL BROOK LATE DRILLED\_12/3/96\_TOTAL DEPTH OF HOLE \_12.0' P-AMETER\_ SCREEN DIA. 2" LENGTH 10.0' SLOT SIZE 0.010" CASING DIA. 2" LENGTH 1.5' TYPE sch 40 pvc I MLLING CO. GMB DRILLING METHOD HSA DRILLER RON GARNEAU LOG BY E. SANDBLOM GRIFFIN INTERNATIONAL, INC BLOWS PER DEPTH WELL DEPTH DESCRIPTION/SOIL CLASSIFICATION NOTES 6" OF SPOON IN CONSTRUCTION IN (COLOR, TEXTURE, STRUCTURES) PEET FEET & PID READINGS ROAD BOX LOCKING WELL CAP 0 . CONCRETE Dry, brown, medium to fine SAND and BENTONITE 1 -0'-5' SILT with gravel 0.2 ppm 2 . WELL RISER 2.5' WATER TABLE 3 3 -4 SAND PACK 5 5'-7'- 15/11/12/13 Multi colored, medium to coarse SAND . 6 and GRAVEL 0.8 ppm 7 WELL SCREEN - 8 -- 8 - 9 -- 9 --10 · 10'-12'- 10/9/6/7 Saturated, brown, fine SAND, SILT and BOTTOM CAP -i1 · -11 · 0.2 ppm CLAY with trace of fine gravel. 12 BASE OF WELL AT 12.0' UNDISTURBED NATIVE SOIL END OF EXPLORATION AT 12.0' -13 -14 -15 · -15 L-16 -16 -17. -17 **-**18 · -18 -19 -19 20 -20 -21 --21 22 22 .23 -23 24 24 -25 -25

WELL NUMBER MW4 PROJECT MAD RIVER GLEN COOPERATIVE Site LOCATION FAYSTON, VERMONT Sketch MILL BROOK DATE DRILLED\_12/3/96 TOTAL DEPTH OF HOLE 12.0' Ø<sup>NT4</sup> DIAMETER\_ SCREEN DIA. 2" LENGTH 7.0' SLOT SIZE 0.010" Ø<sup>MW3</sup> CASING DIA. 2" LENGTH 2.5' TYPE sch 40 pvc DRILLING CO. GMB DRILLING METHOD HSA DRILLER RON GARNEAU LOG BY E SANDBLOM GRIFFIN INTERNATIONAL, INC WELL DEPTH BLOWS PER DESCRIPTION/SOIL CLASSIFICATION DEPTH NOTES IN CONSTRUCTION 6" OF SPOON IN (COLOR, TEXTURE, STRUCTURES) FEET FEET & PID READINGS ROAD BOX LOCKING WELL CAP 0 . CONCRETE · 1 · 0'-5' Medium to fine SAND and SILT with BENTONITE trace of fine gravel. 0.4 ppm 1 2 -3 3 WELL RISER 4 4 5 SAND PACK 5 Well sorted, fine, medium and coarse SAND, some gravel and trace of silt. - 6 5'-7'- 9/4/15/100 6 1.2 ppm 6.5' WATER TABLE 7 WELL SCREEN 7 - 8 -8 -- 9 -BOTTOM CAP 9 --10 -10'-10.25' -10 Saturated SAND and SILT with gravel. 2.1 ppm BEDROCK BASE OF WELL AT 10.0' -11 · REFUSAL AT 10.25' -12 --12 --13 --13 -14 --14 -15 · -15 -16 --16 -17 -17 -18 --18 · -19 --19 -20 -20 -21 -21 -22 -22 23 23 24 -24 25 25

PROJECT MAD RIV	ER GLEN COOPE	RATIVE	WELL NUMBER_s	B1
CATION FAYSTON			Site Sketch	
שATE DRILLED 12/4	•	 EPTH OF HOLE	13.0'	SB1
TIAMETER				$\neg \uparrow$
SCREEN DIA. NA 1	ENGTH NA	SLOT SIZE NA	BASE LODGE	
CASING DIA. NA L				
RILLING COG		• .		$\int \int$
DRILLER RON GARN	EAU_LOG BY	E. SANDBLOM	COURTE INTERNATIONA	
	Τ	<u> </u>	GRIFFIN INTERNATIONAL	J, INC
DEPTH WELL IN CONSTRUCTION	NOTES	BLOWS PER 6" OF SPOON & PID READINGS	DESCRIPTION/SOIL CLASSIFICATION (COLOR, TEXTURE, STRUCTURES)	DEPTH IN FEET
0	7			-0-
			Dry, brown, medium to fine SAND and	1 -
2-4////////////////////////////////////	· ·	, ,	SILT with trace of gravel.	- 2 -
3 <i>- [[[[[[]]]]]</i>				- 3 -
4 - 4 - 4 -				4 -
5	NATIVE		-	- 5 -
- 6 - <b>/////////////////////////////////</b>	BACKFILL	5'-7'- 2/1/1/1	No recovery.	-6-
-7				7-
7-8- <i>4///////////////////////////////////</i>		7'-9' 0 ppm	Saturated, medium to fine GRAVEL, various rock types, till, with silt.	-8-
- 9 - <i>                       </i>			Various fire to modium whele and	- 9 -
-10 - <b>///////////////////////////////////</b>		9'-11'- 12/37/34/38 0.2 ppm	Various fine to medium, whole and fragmented GRAVEL and very fine SAND and SILT.	-10 -
				-11 -
12		11'-13'- 73/69/49/84 11.5'- 0 ppm	12.0' WATER TABLE V	-12 -
13	UNDISTURBED NATIVE SOIL	13.0'- 0.2 ppm	Stratified, orange/gray crushed ROCK with quartz over saturated silty sand.	-13 -
			END OF EXPLORATION AT 13.0'	14 -
15 -			·	-15 -
				-16 -
-17-				-17-
_ <del>_</del>				-18
-19 <b>-</b>				-19
				-20- -21 -
-21 - L <sub>22</sub>				-22-
_ <del> </del> -22-  -23-				-23-
				-24-
-24-  -25-				-25-
			<u></u>	

A CONTRACT OF THE PARTY OF THE

# APPENDIX C GROUNDWATER QUALITY SUMMARY DATA

# Groundwater Quality Data Summary Mad River Glen Coop Fayston, Vermont

# Monitoring Well 1 (MW-1)

	Date of Sam	ple Collection				
PARAMETER	12/12/96		·	1		
Benzene	ND<1					
Chlorobenzene	ND<1			· · · · · · · · · · · · · · · · · · ·		·
1,2 - Dichlorobenzene	ND<1				· · · · · · · · · · · · · · · · · · ·	-
1,3 - Dighlorobenzene	ND<1				•	
1,4 - Dichlorobenzene	ND<1	1. 1.				
Ethylbenzene	ND<1		i ·			
Toluene .	ND<1		<u> </u>	į.		
Xylenes	ND < 1					
Total BTEX - Total BTEX	0.0		1000		- P - 14 - 25 - 24	
MTBE	ND<10			- · ·		
BTEX+MTBE (60 4 5 4 1)	0.0	729 <b>96</b> 0	3 p. 3.			

# Monitoring Well 2 (MW-2)

	Date of Sam	ole Collection	_		·	
PARAMETER	12/12/96	t in the second			-	
Benzene	ND < 1		·			
Chlorobenzene	ND < 1	*				
1,2 - Dichlorobenzene	ND < 1			140		
1,3 - Dichlorobenzene	ND < 1					
1,4 - Dichlorobenzene	ND<1					
Ethylbenzene	ND < 1					
Toluene	ND < 1	1				
Xylenes	ND < 1					
Total BTEX TOTAL	<b>基金基 0.0</b>					
MTBE	ND<10					
BTEX+MTBE ***	0.0.1卷 雜	### Library			14	

# Monitoring Well 3 (MW-3)

	monitoring train o (inter-o)									
	Date of Sample Collection									
PARAMETER	12/12/96	\$ * . · · · .								
Benzene	TBQ<1			<u> </u>						
Chlorobenzene	ND<1		·							
1,2 - Dichlorobenzene	ND<1									
1,3 - Dichlorobenzene	ND<1									
1,4 - Dichlorobenzene	ND<1									
Ethylbenzene	ND<1	·	1			<u> </u>				
Toluene	TBQ<1		· .	-		·				
Xylenes	2.3									
Total BTEX	2.3		15.7235			<b>《春日》 为</b> 以				
MTBE	ND < 10				<u> </u>	·				
BTEX+MTBE	*#**±2.3									

# Groundwater Quality Data Summary Mad River Glen Coop Fayston, Vermont

# Monitoring Well 4 (MW-4)

	Date of Sample Collection							
PARAMETER	12/12/96							
Benzene	TBQ < 1							
Chlorobenzene	ND<1							
1,2 - Dichlorobenzene	ND < 1	<u>.</u>	1, 11, 14, 14					
1,3 - Dichlorobenzene	ND < 1			:	l			
1,4 - Dichlorobenzene	ND < 1							
Ethylbenzene	ND < 1							
Toluene	1.1				·			
Xylenes	ND<1				·			
Total BTEX Consideration	. A. B.				HATE OF SHIPMAN	Separate Separate		
MTBE	ND<10		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1					
BTEX-MTBE & TALE OF	45i#731	Merce - Ca			1924			

# Base Box SW

	Date of Sample Collection								
PARAMETER	12/12/96		ara arabicia						
Benzene	ND<1		s a la la managara.						
Chlorobenzene	ND < 1								
1,2 - Dichlorobenzene	ND<1								
1,3 - Dichlorobenzene	ND<1								
1,4 - Dichlorobenzene	ND<1	<u></u> . ,							
Ethylbenzene	ND < 1								
Toluene	ND < 1	· .		<u> </u>					
Xylenes	ND < 1					ļ			
Total BTEX ****		ut la la	200	Talk diese au		40 300			
MTBE	ND<10	18 - 1 - 1							
BTEX+MTBE ************************************	0.0	- 18 A - 18 E		11.00	Try William to	14.2 ************************************			

# Patrol/Nursery SW

	Date of Sam	ple Collection	Now ware the			
PARAMETER	12/12/96			j.		
Benzene	ND<1					
Chlorobenzene	ND<1					
1,2 - Dichlorobenzene	ND<1				·	
1,3 - Dichlorobenzene	ND<1	- <del></del> -				
1,4 - Dichlorobenzene	ND<1					
Ethylbenzene	ND < 1					
Tolue <b>ne</b>	ND<1			<u> </u>	1	
Xylenes	ND < 1		-			
Total BTEX : TOTAL BTEX :	- ¥ 94,0.0				GRALES AS	
MTBE	ND<10					
BTEX+MTBE * #32 #12	0.0 等料公益		40000000			14-14 - A

All values reported in ug/L (ppb) ND - Non Detect

TBQ - Trace Below Quantitation Limit

# Groundwater Quality Data Summary Mad River Glen Coop Fayston, Vermont

Vermont Drinking Water Standards and Quality Assurance and Control Samples

Sample Date: December 12, 1996

	Equipment	Trip	Duplicate	Vermont Drinking
PARAMETER	Blank	Blank	(MW-2)	Water Standards
Benzene	N/A	ND < 1	ND<1	5.0*
Chlorobenzene	N/A	ND<1	ND<1	100*
1,2 - Dichlorobenzene	N/A	ND<1	ND<1	600*
1,3 - Dichlorobenzene	N/A	ND<1	ND<1	600**
1,4 - Dichlorobenzene	N/A	ND<1	ND<1	75*
Ethylbenzene	N/A	ND < 1	ND < 1	700*
Toluene	N/A	1.1	ND < 1	1,000*
Xylenes	N/A	TBQ<1	ND<1	10,000*
Total BTEX / Harry	AN NA	9727 776	<b>4888 £0.0</b>	
МТВЕ	N/A	ND<10	ND<10	40**
BTEX#MTBE	N/A		0.0	

# APPENDIX D SOIL SAMPLE ANALYSIS DATA SUMMARY

# Soil Sample Analysis Data Summary Mad River Glen Coop Fayston, Vermont

# SB-1 (12' Below Ground Surface)

	Date of Sample Collection								
PARAMETER	12/4/96								
Benzene	ND<51					1			
Chlorobenzene	ND<51								
1,2 - Dichlorobenzene	ND<51								
1,3 - Dichlorobenzene	ND<51								
1,4 - Dichlorobenzene	ND < 51								
Ethylbenzene	ND<51				, i				
Toluene	ND<51								
Xylenes	ND<51						1		
Total BTEX (### 大學 /)	9.03%第二条	-226.23		<b>7</b> 2-2-2					
MTBE	ND<510								
BTEX+MTBE	} =: 0:0				- 一流電	* (1)	10 To 100		

# APPENDIX E GROUNDWATER LIQUID LEVEL DATA

1/10/97

# Liquid Level Monitoring Data Mad River Glen Coop Fayston, Vermont

# Monitoring Date: 12-Dec-96

Well I.D.	Well Depth	Top of Casing Elevation	Depth to Product	Depth to Water	Product Thickness	Specific Gravity of Product	Hydro Equivalent	Corrected Depth to Water	Corrected Water Table Elevation
MW-1	12.50	100.00	-	7.42	-	-	-	7.42	92.58
MW-2	10.00	101.49	•	3.82	-	-	-	3.82	97.67
MW-3	12.00	98.71		2.32	-	-	-	2.32	96.39
MW-4	10.00	95.14		6.57	-	-	-	6.57	88.57
				<u> </u>	<u> </u>				

1/10/97

# Historical Groundwater Elevation Data Mad River Glen Coop Fayston, Vermont

Well		Monitoring Date:									
No.	12/12/96	1 1	1	1	1		1	i	I	1	
•.	· · · · · · · · · · · · · · · · · · ·				<u> </u>	<del>                                     </del>				<u> </u>	
MW-1	92.58	1						<del></del> -	-	<del> </del>	
MW-2	97.67			<u> </u>					<del>                                     </del>	<del></del>	
MW-3	96.39			77		<del></del>	<del></del>	<del> </del>		<del> </del>	
MW-4	88.57		<u> </u>	<del>                                     </del>				<u> </u>	<del> </del>	<del> </del>	
		<u> </u>		1		1		<del></del>			

# APPENDIX F LABORATORY ANALYSIS REPORTS



## **Laboratory Services**

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

# REPORT OF LABORATORY ANALYSIS

**CLIENT:** Griffin International

PROJECT NAME: Mad River Glen Coop

REPORT DATE: December 18, 1996
DATE SAMPLED: December 12, 1996

PROJECT CODE: GIMR1309

REF.#: 97,850 - 97,857

Enclosed please find the results of the analyses performed for the samples referenced on the attached chain of custody. Chain of custody indicated sample preservation with HCl.

All samples were prepared and analyzed by requirements outlined in the referenced method and within the specified holding times. All instrumentation was calibrated with the appropriate frequency and verified by the requirements outlined in the referenced method. Blank contamination was not observed at levels affecting the analytical results.

Analytical method precision and accuracy was monitored by laboratory control standards which included matrix spike, duplicate and quality control analyses. These standards were determined to be within established laboratory method acceptance limits.

Individual sample performance was monitored by the addition of surrogate analytes to each sample. All surrogate recovery data was determined to be within laboratory QA/QC guidelines unless otherwise noted.

Reviewed by,

Harry B. Locker, Ph.D. Laboratory Director

enclosures



## **Laboratory Services**

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

# **EPA METHOD 602-PURGEABLE AROMATICS**

CLIENT: Griffin International

DATE RECEIVED: December 12, 1996

PROJECT NAME: Mad River Glen Coop

REPORT DATE: December 18, 1996

CLIENT PROJ. #: 11964945

PROJECT CODE: GIMR1309

Ref. #:	97,850	97,851	97,852	97,853	97,854		
Site:	Trip Blank	MW-1	MW-2	MW-3	MW-4		
Date Sampled:	12/12/96	12/12/96	12/12/96	12/12/96	12/12/96		
Time Sampled:	8:12	10:08	10:10	10:05	9:56		
Sampler:	E.S./S.B.	E.S./S.B.	E.S./S.B.	E.S./S.B.	E.S./S.B.		
Date Analyzed:	12/17/96	12/16/96	12/16/96	12/17/96	12/17/96		
UIP Count:	0	o	0	5	4		
Dil. Factor (%):	100	100	100	100	100		
Surr % Rec. (%):	92	95	95	96	94		
Parameter	Conc. (ug/L)						
Benzene	<1	<1	<1	TBQ <1	TBQ <1		
Chlorobenzene	<1	· <1	<1	′ <1	<1		
1,2-Dichlorobenzene	<1	<1	<1	<1	<1		
1,3-Dichlorobenzene	<1	<1	<1	<1	<1		
1,4-Dichlorobenzene	<1	<1	<1	<1	<1		
Ethylbenzene	<1	<1	<1	<1	<1		
Toluene	1.1	<1	<1	TBQ <1	1.1		
Xylenes	TBQ <1	<1	. <1	2.3	<1		
MTBE	<10	<10	<10	<10	<10		

Ref. #:	97,855	07.057	1 02.052	<u> </u>
Site:	· ·	97,856	97,857	i i
	Duplicate	Patrol SW	Base Box SW	1
Date Sampled:	12/12/96	12/12/96	12/12/96	1
Time Sampled:	10:10	11:25	11:31	
Sampler:	E.S./S.B.	E.S./S.B.	E.S./S.B.	1
Date Analyzed:	12/16/96	12/16/96	12/16/96	1
UIP Count:	0	0	0	
Dil. Factor (%):	100	100	100	
Surr % Rec. (%):	96	96	. 96	
Parameter	Conc. (ug/L)	Conc. (ug/L)	Conc. (ug/L)	
Benzene	<1	. <1	<1	
Chlorobenzene	<1	<1	<1	
1,2-Dichlorobenzene	<1	<1	<1	<b>!</b> .
1,3-Dichlorobenzene	<1	<1	<1	i l
1,4-Dichlorobenzene	<1	<1	<1	i
Ethylbenzene	<1	· <1	<1	
lents a				
Toluene	<1	<1	<1	
Toluene Xylenes	<1 <1	<1 <1	<1 - <1	

Note: UIP = Unidentified Peaks TBQ = Trace Below Quantitation NI = Not Indicated

TEE! TYNE, b. 1 1 1 1 1 1 1 1 20-70 1

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333

110124015

# CHAIN-OF-CUSTODY RECORD

Project Name: Not River Glen Cools Site Location: Fayston, UT	Reporting Address: Griffin		Billing Address:					
Endyne Project Number: GIMR1309	Company: 60 124 1 Contact Name/Phone #: 5. Sond	ppw	Sampler Name: E. Scole Dom B. Bombordies Phone #: 865-4288					
Lab# Sample Location Mai	rix R O Date/Time No.	le Containers F	<b>  _   _   _   _   _   _   _   _   _   _</b>	malysis Sample Preservation Rush				
97,850 Trip Blank Hz		40ml		ALCE Hel.				
95,85/ MW-1	1 1008 1	1		1 1				
92.852 MW-Z	1010							
95,853 MW-3	1005							
7%854 NW-4		<del>                                     </del>						
	956							
17.855 Diplicate	1010		· · · · · · · · · · · · · · · · · · ·					
93856 Patrol Sw	1175							
92857 Bessebox SW 1	11:31			1 /				
				· · · · · · · · · · · · · · · · · · ·				
Relinquished by: Signature	Received by: Signature Bully	044	Date/Time 12/12/94 1730					
		77						
Relinquished by: Signature Con	Received by: Signature Feelann	Blesser	Date/Time /2/13/96	10:05AM				
New York State Project: Yes No	Requested Analys	ses						
1 pH 6 TKN	11 Total Solids 16	Metals (Specify)	21 EPA 624	26 EPA 8270 B/N or Acid				
2 Chloride 7 Total P	12 TSS 17	Coliform (Specify)	22 EPA 625 B/N or A	27 EPA 8010/8020				
3 Ammonis N 8 Total Diss. P	13 TDS 18	COD	23 EPA 418.1	28 EPA 8080 Pest/PCB				
4 Nitrite N 9 BOD,	14 Turbidity 19	BTEX	24 EPA 608 Pen/PCB					
5 Nitrate N 10 Alkalinity	15 Conductivity 20	EPA 601 602	25 EPA 8240					
29 TCLP (Specify: volutiles, semi-volutiles, metals, pesticides, herbicide								
30 Other (Specify):								



# **Laboratory Services**

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

# REPORT OF LABORATORY ANALYSIS

CLIENT: Griffin International

PROJECT NAME: Mad River Glen Coop

REPORT DATE: December 13, 1996
DATE SAMPLED: December 3, 1996

PROJECT CODE: GIMR1198

REF.#: 97,541

Enclosed please find the results of the analyses performed for the samples referenced on the attached chain of custody. Chain of custody indicated proper sample preservation.

All samples were prepared and analyzed by requirements outlined in the referenced method and within the specified holding times. All instrumentation was calibrated with the appropriate frequency and verified by the requirements outlined in the referenced method. Blank contamination was not observed at levels affecting the analytical results.

Analytical method precision and accuracy was monitored by laboratory control standards which included matrix spike, duplicate and quality control analyses. These standards were determined to be within established laboratory method acceptance limits.

Individual sample performance was monitored by the addition of surrogate analytes to each sample. All surrogate recovery data was determined to be within laboratory QA/QC guidelines unless otherwise noted.

Reviewed by,

Harry B. Locker, Ph.D. Laboratory Director

enclosures



# **Laboratory Services**

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

## **EPA METHOD 602--PURGEABLE AROMATICS**

CLIENT: Griffin International

DATE RECEIVED: December 4, 1996

PROJECT NAME: Mad River Glen Coop

REPORT DATE: December 13, 1996

CLIENT PROJ. #: NI

PROJECT CODE: GIMR1198

Ref. #:	97,541	<u></u>	1	<u> </u>	··
Site:	SB1 12' BGS				
Date Sampled:	12/4/96				·
Time Sampled:	10:04			1	
Sampler:	E. Sandblom		1	İ	
Date Analyzed:	12/13/96				
UIP Count:	0		•		. ·
Solids (%):	87	i		<b>!</b>	•
Surr % Rec. (%):	107			İ	
Parameter	ug/kg, wet wt.			1	<del>""</del>
Benzene	<51		T		
Chlorobenzene	<51			<b>]</b>	
1,2-Dichlorobenzene	<51		1	ĺ	
1,3-Dichlorobenzene	<51		ĺ		
1,4-Dichlorobenzene	<51				
Ethylbenzene	<51				
Toluene	<51				
Xylenes	<51				
MTBE	<510				

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333

# CHAIN-OF-CUSTODY RECORD

Project Name: MAD RIVER GLEN COOP Site Location: FAYSTON, VT					Reporting Address:  CEIFFIN						Billing Address:  GRIFFIN									
Endyne Project Number: GIMR 1198						Company: GRIFFIN Contact Name/Phone #: E SANDBLOM						Sampler Name: E. SANDELCM Phone #: 845 - 4288								
Lab	Lab# Sample Location Ma			Mate	trix R O Date/Time A M P /Z/14/9/1		Sample Containers No.   Type/Size				Field Results/Remarks			Analysis Sample Required Preservation						
925	4/ 5	B-/	IZ	'B	.6,	#GG	<i>,;]</i>	X	2200 F3200	10:04	*****	***** Z	ZECML				27		4°C	
,		, and a												· ·						
											$\neg$									
							$\top$	-										$\dashv$		
																			· · · · · ·	
						<u> </u>									<del></del>				<del></del>	<del></del>
<del></del>						<u> </u>	_											<del></del>		···
*****									_					·	$\dashv$					
			· ·		<del></del>															
·			1	1			··		-				<del></del>							
						<u> </u>					$\dashv$	~						$\dashv$		<u> </u>
<del></del>			····			<b></b>	$\neg$				$\dashv$									
			<i>Λ</i> Τ		<del>-   -   -   -   -   -   -   -   -   -  </del>	<u> </u>			<u> </u>	.~7.		<u></u>		<del></del>	<del></del>				<u> </u>	
Kelingu	ished by:	Signature 4	W-C		7/L		Received by: Signature Busey-Cu						,	Date/Time 12/4/910 15:55						
Relinquished by Signature				Received by: Signature M. Chambers					Date/Time 12-5-96 10:05											
New Yor	k State l	Project; Y	(es	_ No	<u>_X</u> _					Requeste	d Ana	lys	es							
1	ρΉ			6	TKN		11		otal Solida	ls	16		Metals (Specify)		21	EPA 624	26	EP/	\ 8270 B/N or A	cid
2	Chloride			7	Total P	<b></b>	12		TSS		17	٠.	Coliform (Specify)		22 EPA 625 B/N or A		27	27 EPA 8010/(020)		
3	Ammoni Nitrite N		<del>  -</del>	8	Total Diss. P		13 14		TDS		18		COD			23 EPA 418.1		28 EPA 8080 Pest/PCB		3
5	Nitrate N			10	BOD, Alkalinity		15			19 20		BTEX EPA 601/602		24 EPA 608 Pest/PCB						
29			iles, semi-v		, metals, pesticides, 1	nerbicides)	Ц	`		·-	II		2.7.401/002		25	EPA 8240		<u> </u>	<del> </del>	
30	Other (S																		<u></u>	